

February 3, 2012

Pre-bid ecomaine elevator repair clarification:

During the pre-bid, there were several questions on the configuration of the new fire alarm systems currently being installed relative to the elevator interfaces. The following summary was received from the alarm installation contractor:

“SimplexGrinnell is providing a new smoke sensor at each elevator lobby (on the office side) and heat sensor at each elevator level (on the plant side). Additionally, we are providing a smoke and heat sensor in the elevator control room and four (4) control modules to be interfaced to elevator controller for designated level recall (primary), alternate level recall (secondary), shunt trip and fire fighter hat.

Note: The Elevator Inspector prefers that the smoke & heat sensor, typically installed at the top of a sprinkled elevator shaft, not be installed and therefore are not being provided.”